KOLAR DIVISION.

[ADVERTISEMENT.

Notification, dated 25th April 1896.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kolar Division, up to 30th May 1896, for constructing a new Taluk Cutcherry at Mulbagal. An approximate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of 20th June 1897.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Kolar between the hours of 11 A. M. to 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory notes, as earnest money, and be superscribed "Tender for constructing a new Taluk Cutcherry at Mulbagal;" in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

	Description of work.	*Per.*	*Quantity.*
1	Earthwork and filling basement	C. yds.	815
2	Stone in chunam	C. ft.	15·413
3	Burnt brick in chunam	„	14·387
4	Ditto arch-work	„	571
5	Stone slabs for steps	R. ft.	96
6	Ditto	Sq. ft.	971
7	Ditto 9″ thick	Sq. ft.	59
8	Dental cornice	R. ft.	90
9	Plain cornice	„	76
10	Cornice over plinth of piers	„	45
11	Ornamental finials	Each.	4
12	Teakwood work wrought and put up	C. ft.	367
13	Roofing with Mangalore tiles and teak-reepers	Sqre.	53·50
14	Bengal terracing with three courses of flat tiles and chunam plaster including reepers, nails, &c.	„	18·26
15	Pucka terrace	„	1·00
16	Flooring with flag stones including trimming joint and fixing in mortar...	„	13·04
17	Flooring with concrete	„	18·00
18	Flooring with gravel	„	5·98
19	Plastering with mortar.	„	235·72
20	White-washing }	„	235·72
21	Color-washing }		
22	Doors, battened teak $\frac{3\times5\times6}{20\times3\times6}$	Sq. ft.	486
23	Windows with battened and glazed shutters and iron bars	„	63
24	Windows with battened and glazed shutters with iron bars $13\times3\times3\frac{1}{2}$ ..	„	136
25	Ventilators with iron bars inside to inside of panes $7\times\frac{2\frac{1}{2}\times1}{9\times2\times1}$	„	101
26	Seevers	„	18
27	Entrance gate	Each	1
28	Brick in chunam pillars	Lumpsum.	
29	Painting	Sqre.	17·14
30	White-ant composition	Sqre.	20·00
31	Wood oiling	Sqre.	30·00
32	Shelves for record rooms	Lumpsum.	
33	Zinc shutters for roof valley	Do	
34	Matting	Sqre.	18·00

C. M. ANANDAIHETHA RAO,
Offg. Executive Engineer.